

**AAMA 1503-09 THERMAL PERFORMANCE
TEST REPORT**

Rendered to:

CMI ARCHITECTURAL PRODUCTS, INC.

SERIES/MODEL: 450TB - Center Glazed

TYPE: Glazed Wall Systems (Site-built)

Summary of Results		
Thermal Transmittance (U-Factor)		0.37
Condensation Resistance Factor - Frame (CRF _f)		64
Condensation Resistance Factor - Glass (CRF _g)		72
Unit Size:	78-7/8" x 78-1/2"	
Layer 1:	1/4"	SolarBan 60 Low-E (e=0.035*, #2)
Gap 1:	0.50"	A1-D: Aluminum Spacer
Layer 2:	1/4"	Clear
		90% Argon*

Reference must be made to Report No. C5085.02-201-46, dated 12/11/13 for complete test specimen description and data.

AAMA 1503-09 THERMAL PERFORMANCE TEST REPORT

Rendered to:

CMI ARCHITECTURAL PRODUCTS, INC.
2800 Freeway Blvd Ste 205
Minneapolis, Minnesota 55430

Report Number: C5085.02-201-46
Test Date: 12/11/13
Report Date: 12/11/13
Test Record Retention End Date: 12/11/17

Test Sample Identification:

Series/Model: 450TB - Center Glazed

Type: Glazed Wall Systems (Site-built)

Test Sample Submitted by: Client

Test Procedure: The condensation resistance factor (CRF) and thermal transmittance (U) were determined in accordance with AAMA 1503-09, *Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections*

- | | |
|---|---------|
| 1. Average warm side ambient temperature | 69.80 F |
| 2. Average cold side ambient temperature | -0.39 F |
| 3. 15 mph dynamic wind applied to test specimen exterior. | |
| 4. 0.0" \pm 0.04" static pressure drop across specimen. | |

Test Results Summary:

- | | |
|---|------|
| 1. Condensation resistance factor - Frame (CRF _f) | 64 |
| Condensation resistance factor - Glass (CRF _g) | 72 |
| 2. Thermal transmittance due to conduction (U) | 0.37 |
| (U-factors expressed in Btu/hr·ft ² ·F) | |

Test Sample Description:

Frame:

Material:	AT (0.212"): Aluminum with Thermal Breaks - All Members		
Size:	78-7/8" x 78-1/2"		
Daylight Opening:	36-1/8" x 74-1/8" (x2)	Glazing Method:	Exterior
Exterior Color:	Gray	Exterior Finish:	Paint
Interior Color:	Gray	Interior Finish:	Paint
Corner Joinery:	Square Cut / Screws / Unsealed		

Glazing Information:

Layer 1:	1/4"	SolarBan 60 Low-E (e=0.035*, #2)	
Gap 1:	0.50"	A1-D: Aluminum Spacer	90% Argon*
Layer 2:	1/4"	Clear	
Gas Fill Method:	Single-Probe Method*		
Desiccant:	Yes		

**Stated per Client/Manufacturer*

N/A Non-Applicable

Test Sample Description: (Continued)

Weatherstripping:

Description	Quantity	Location
No weatherstrip		

Hardware:

Description	Quantity	Location
No hardware		

Drainage:

Description	Size	Quantity	Location
No drainage			

Test Duration:

1. The environmental systems were started at 14:25 hours, 12/10/13.
2. The thermal performance test results were derived from 03:05 hours, 12/11/13 to 07:05 hours, 12/11/13.

Condensation Resistance Factor (CRF):

The following information, condensed from the test data, was used to determine the condensation resistance factor:

T_h	=	Warm side ambient air temperature	69.80 F
T_c	=	Cold side ambient air temperature	-0.39 F
FT_p	=	Average of pre-specified frame temperatures (14)	44.53 F
FT_r	=	Average of roving thermocouples (4)	40.60 F
W	=	$[(FT_p - FT_r) / (FT_p - (T_c + 10))] \times 0.40$	0.045
FT	=	$FT_p(1-W) + W (FT_r) = \text{Frame Temperature}$	44.31 F
GT	=	Glass Temperature	49.88 F
CRF_g	=	Condensation resistance factor – Glass	72
		$CRF_g = (GT - T_c) / (T_h - T_c) \times 100$	
CRF_f	=	Condensation resistance factor – Frame	64
		$CRF_f = (FT - T_c) / (T_h - T_c) \times 100$	

The CRF number was determined to be 64 (on the size as reported). When reviewing this test data, it should be noted that the frame temperature (FT) was colder than the glass temperature (GT) therefore controlling the CRF number. Refer to the 'CRF Report' page and the 'Thermocouple Location Diagram' page of this report.

Thermal Transmittance (U_c):

T_h	= Average warm side ambient temperature	69.80 F
T_c	= Average cold side ambient temperature	-0.39 F
P	= Static pressure difference across test specimen	0.00 psf
	15 mph dynamic perpendicular wind at exterior	
	Nominal sample area	43.00 ft ²
	Total measured input to calorimeter	1231.65 Btu/hr
	Calorimeter correction	108.32 Btu/hr
	Net specimen heat loss	1123.34 Btu/hr
U	= Thermal Transmittance	0.37 Btu/hr·ft ² ·F

Glazing Deflection:

	Left Glazing	Right Glazing
Edge Gap Width	0.50"	0.50"
Estimated center gap width upon receipt of specimen in laboratory (after stabilization)	0.49"	0.58"
Center gap width at laboratory ambient conditions on day of testing	0.49"	0.58"
Center gap width at test conditions	0.41"	0.57"

The sample was inspected for the formation of frost or condensation, which may influence the surface temperature measurements. The sample showed no evidence of condensation/frost at the conclusion of the test.

Prior to testing the specimen was sealed with silicone on the interior side and checked for air infiltration per Section 9.3.4.

Required annual calibrations for the Architectural Testing Inc. 'thermal test chamber' (ICN N000235) in St. Paul, Minnesota were last conducted in September 2012 in accordance with Architectural Testing Inc. calibration procedure. A CTS Calibration verification was performed November 2012. A Metering Box Wall Transducer and Surround Panel Flanking Loss Characterization was performed September 2012.

CRF Report

Time:	05:05	05:35	06:05	06:35	07:05	AVERAGE
--------------	-------	-------	-------	-------	-------	---------

Pre-specified Thermocouples - Frame

1	37.41	37.42	37.42	37.41	37.41	37.42
2	40.65	40.61	40.65	40.66	40.64	40.64
3	40.18	40.19	40.20	40.19	40.19	40.19
4	47.90	47.90	47.94	47.93	47.91	47.92
5	42.46	42.46	42.45	42.50	42.41	42.45
6	46.65	46.66	46.66	46.67	46.67	46.66
7	47.12	47.15	47.14	47.16	47.14	47.14
8	49.09	49.08	49.09	49.09	49.10	49.09
9	45.30	45.31	45.31	45.33	45.30	45.31
10	47.20	47.18	47.20	47.22	47.21	47.20
11	42.90	42.92	42.92	42.96	42.90	42.92
12	44.22	44.21	44.26	44.27	44.28	44.25
13	46.12	46.14	46.14	46.16	46.15	46.14
14	46.07	46.09	46.09	46.10	46.06	46.08
FT _P	44.52	44.52	44.53	44.55	44.53	44.53

Pre-specified Thermocouples - Glass

15	37.31	37.34	37.36	37.36	37.33	37.34
16	55.33	55.33	55.32	55.35	55.31	55.33
17	46.57	46.58	46.58	46.57	46.56	46.57
18	51.27	51.28	51.27	51.31	51.29	51.28
19	58.19	58.19	58.21	58.18	58.18	58.19
20	50.55	50.63	50.61	50.58	50.62	50.60
GT	49.87	49.89	49.89	49.89	49.88	49.88

Cold Point (Roving) Thermocouples

21	37.41	37.42	37.42	37.41	37.41	37.41
22	40.65	60.61	40.65	40.66	40.64	44.64
23	40.18	40.19	40.20	40.19	40.19	40.19
24	40.16	40.14	40.13	40.15	40.15	40.15
FT _R	39.60	44.59	39.60	39.60	39.60	40.60
W	0.06	0.00	0.06	0.06	0.06	0.05
FT	44.24	44.52	44.25	44.27	44.25	44.31

Warm Side - Room Ambient Air Temperature


69.78	69.79	69.81	69.81	69.81	69.80
-------	-------	-------	-------	-------	-------

Cold Side - Room Ambient Air Temperature





-0.40	-0.34	-0.39	-0.41	-0.44	-0.39
-------	-------	-------	-------	-------	-------

CRF _f	64	64	64	64	64	64
CRF _g	72	72	72	72	72	72

Thermocouple Location Diagram



Cold Point Locations

	21. 37.41
	22. 44.64
	23. 40.19
	24. 40.15

Detailed drawings, data sheets, representative samples of test specimens, a copy of this report, or other pertinent project documentation will be retained by Architectural Testing, Inc. for a period of four years from the original test date. At the end of this retention period such materials shall be discarded without notice and the service life of this report by Architectural Testing will expire. Results obtained are tested values and were secured by using the designated test methods. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, INC.

Greg S. Borchers
Technician

Michael P. Resech
Manager - Simulations and Thermal Testing
Individual-In-Responsible-Charge

GSB:gsb
C5085.02-201-46


Attachments (pages): This report is complete only when all attachments listed are included.

Appendix-A: Drawings (1)

Revision Log

Rev. #	Date	Page(s)	Revision(s)
02-R0	12/11/13	All	Original Report Issue. Work requested by Philip Leonard of CMI Architectural Products, Inc.

Appendix A: Drawings







450TB-CG THERMAL TEST
1 THUS
450TB-CG (2" x 4 1/2")
1" GLAZING
SCALE: 1/2"=1'-0"

GLASS TYPE:
CLEAR 1" INSULATED GLASS UNITS
1/4" CLEAR WITH PPG SOLARBAN 60 SOLAR CONTROL LOW-E #2 ANNEALED
1/2" AIRSPACE - ALUMINUM SPACER / 90% ARGON FILLED
1/4" CLEAR ANNEALED
GLASS SIZE = 2 PIECES 37 1/8" x 75 1/8"

TESTING PARAMETERS:
AAMA 1503-09 VOLUNTARY TEST METHOD FOR THERMAL TRANSMITTANCE AND CONDENSATION RESISTANCE OF WINDOWS, DOORS AND GLAZED CURTAIN WALL SECTIONS.
NFRC 102-2010 PROCEDURE FOR MEASURING THE STEADY STATE THERMAL TRANSMITTANCE OF FENESTRATION SYSTEMS.
AAMA 507-03 STANDARD PRACTICE FOR DETERMINING THE THERMAL PERFORMANCE CHARACTERISTICS OF FENESTRATION SYSTEMS INSTALLED IN COMMERCIAL BUILDING.
- STANDARD AAMA 507 INSULATED GLASS
UNIT COMPOSITION WITH ALUMINUM SPACER

NOTES:
FACTORY INSTALL FRAME IN WOOD BUCK PERIMETER
FACTORY INSTALL GLAZING
FACTORY INSTALL EXTERIOR AND INTERIOR PERIMETER CAULK SEAL TO WOOD BUCK PERIMETER
FACTORY INSTALL TEMPORARY DIAGONAL WOOD BRACING FOR SHIPPING PROTECTION.



CMI Architectural
CMI-ARCHITECTURAL PRODUCTS, INC.
20621 HWY 25 N.
Dakota, South Dakota 57231
TELEPHONE (605)854-3326
FAX (605)854-3620

THIS DRAWING IS PREPARED FOR THE SOLE USE OF OBTAINING APPROVAL FOR MATERIAL SHOWN. CMI-ARCHITECTURAL ASSUMES NO RESPONSIBILITY FOR GLASS SIZES, DETAILS OR MATERIALS SPECIFIED BY OTHERS. THE USER OF THESE DRAWINGS SHALL BE RESPONSIBLE FOR THE PROPER AND STRUCTURAL ANCHOR CONDITIONS ARE NOT THE RESPONSIBILITY OF CMI-ARCHITECTURAL. THE RESPONSIBILITY OF THE INSTALLER THESE DRAWINGS ARE THE EXPRESS PROPERTY OF CMI-ARCHITECTURAL.

CMI THERMAL TEST
450TB CENTER GLAZED THERMAL WINDOW TEST

PROJECT: _____
ARCHITECT: _____
GLAZING CONTRACTOR: _____

REVISIONS		
REV	INTL	DATE
▲		
▲		
▲		
▲		
▲		
▲		
▲		
▲		
▲		
▲		

DATE DRAWN: _____
DRAWN BY: _____ SOLD BY: _____
PO#: _____
SCALE: AS NOTED
PROJECT MGR. _____
CMI S.O.# _____
SHEET: 1